



GENERAL NOTES:

- CSA B66 CERTIFIED FRP SEPTIC TANK.
- RATED FOR 2' OF BURIAL DEPTH AND NO TRAFFIC LOADING.
- BAFFLE WALL IS INSTALLED. VOLUMES ARE APPROXIMATE.
- ALL DRILLED HOLES FLANGES TO BE COATED WITH RESIN.
- SAFETY DEVISE CAN WITHSTAND 91 KG. OF DEAD LOAD.
- DIMENSIONS SHOWN IN FEET INCHES FORMAT OTHERWISE NOTED.
- 1/2" FABRICATION TOLERANCE. DOES NOT APPLY TO LAMINATE THICKNESS.

ITEM#	QTY	PART LIST	DESCRIPTION	SHELL THICKNESS:	0.280"	DRAWN:	ATF
1	1	30" CAP LID W/ 8"D POLY SCREW OUT INSERT	FPR LID	DISH HEAD THICKNESS:	0.280"	CHECKED:	
2	1	30"Ø MANWAY COLLAR	30"Ø FRP MANWAY	RIBS THICKNESS:	0.25" WITH 1 WR	DATE:	JULY 05, 2023
3	1	4" PVC-DWV 90°	INLET	WEIGHT:	306KG (675LBS)	DESIGNED:	
4	1	FRP FULL BAFFLE WALL W/ REINFORCEMENT	BAFFLE WALL	LENGTH:	3,048MM (10'-0")	APPROVED:	MPS
5	1	MILD STEEL LUG	LIFT LUG	SEPTIC CHAMBER:	3,159L (695 IG/834 USG)	MFG:	DS
6	1	POLYETHYLENE SAFETY GRATE C/W HARDWARE	SAFETY GRATE	EFFLUENT CHAMBER:	963 L (212 IG/254 USG)	QA:	GA
7				OVERALL CAPACITY:	4,546 L (1,000 IG/1,200 USG)	SALES:	TA

SA

CLIENT: FRP/MOCOAT FIBERGLASS LTD.

TITLE: **P1000-SB FRP PUMPOUT TANK**

FRP MOCOAT
FIBERGLASS LTD.

SIZE: C	DRAWING NUMBER: P1000-SB	REVISION: 0
SCALE: 1:20	WEIGHT:	SHEET: 1/1
BURIAL DEPTH:	RATED 2'-0"	